6 TELESCOPIC SPREADER BEAM





SPECIFICATION

Tare Weight: 0.050t (Excl. slings/shackles)

Lifting lugs (top) suit: 4.7t Grade S bow shackle

Load lugs (lower) suit: 4.7t Grade S bow shackle

Centre lug suits: Self lift only

ASSURANCE

Compliance Standard: AS4991-2004

Proof load tested: Yes

NDT Weld Inspection: Yes

Standard Finish*: Painted (G36 Green)

*Other colours/finishes available on request

Span	WLL (at included sling angle)				Approx. Sling Leg Length (Mtrs)			Approx. Headroom (Mtrs)		
(Mtrs)	60°	90°	120°	CENTRE LIFT	60°	90°	120°	60°	90°	120°
2.0m	6t	3.5t	2t	NA	2.0	1.4	1.1	1.7	1.0	0.6
2.2m	6t	3.5t	2t	NA	2.2	1.6	1.3	1.9	1.1	0.6
2.4m	6t	3.5t	2t	NA	2.4	1.7	1.4	2.1	1.2	0.7
2.6m	6t	3.5t	2t	NA	2.6	1.8	1.5	2.3	1.3	0.8
2.8m	6t	3.5t	2t	NA	2.8	2.0	1.6	2.4	1.4	0.8
3.0m	6t	3.5t	2t	NA	3.0	2.1	1.7	2.6	1.5	0.9





