6 TELESCOPIC SPREADER BEAM





SPECIFICATION

Tare Weight: 0.105t (Excl. slings/shackles)

Lifting lugs (top) suit: 4.7t Grade S bow shackle

Load lugs (lower) suit: 4.7t Grade S bow shackle

Centre lug suits: Self lift only

ASSURANCE

Compliance Standard: AS4991-2004


Proof load tested: Yes

NDT Weld Inspection: Yes

Standard Finish*: Painted (G36 Green)

*Other colours/finishes available on request

| Span | WLL (at included sling angle) | | | | Approx. Sling Leg Length (Mtrs) | | | Approx. Headroom (Mtrs) | | |
|--------|-------------------------------|-----|------|----------------|---------------------------------|-----|------|-------------------------|-----|------|
| (Mtrs) | 60° | 90° | 120° | CENTRE LIFT | 60° | 90° | 120° | 60° | 90° | 120° |
| 3.0m | 6t | 6t | 4.5t | NA | 3.0 | 2.1 | 1.7 | 2.6 | 1.5 | 0.9 |
| 3.5m | 6t | 6t | 4.5t | NA | 3.5 | 2.5 | 2.0 | 3.0 | 1.8 | 1.0 |
| 4.0m | 6t | 6t | 4.5t | NA | 4.0 | 2.8 | 2.3 | 3.5 | 2.0 | 1.2 |
| 4.5m | 6t | 6t | 4.5t | NA | 4.5 | 3.2 | 2.6 | 3.9 | 2.3 | 1.3 |
| 5.0m | 6t | 6t | 4.5t | NA | 5.0 | 3.5 | 2.9 | 4.3 | 2.5 | 1.4 |
| | | | | | | | | | | |



CONTRACT

